Test Case 11

Author Tue Jensen, Kai Heussen (Edmund Widl)
Project SmlLES, ERIGrid 2.0

Version <u>0.2</u> Date <u>2020-12-16</u>

Name of the Test Case	Characterization of power-to-heat service availability and its impact on the networks
Narrative	A network-integrated booster heat pump is used to also provide services to the electrical system. In the local electrical distribution network congestion may appear, and other flexibility options are available.
	This test seeks to characterize the impact of the use of local flexibility on available regulating power from a local district. The test targets an examination of the ability of the system to provide these services when under conflict.
Function(s) under Investigation (Ful) "the referenced specification of a function realized (operationalized) by the object under investigation"	The heating system provides services to the electrical system (a) congestion management - electrical import and export limitation; and (b) regulating power provision.
Object under Investigation (Oul) "the component(s) (1n) that are to be qualified by the test"	The characterization concerns the Booster Heater Controller and the Electric Storage Controller in combination with the District Supervisory Controller.
Domain under Investigation (<i>Dul</i>) "the relevant domains or sub-domains of test parameters and connectivity."	 power (low voltage distribution network) heat (coupling points to thermal network) control (storage and heat network control)
Purpose of Investigation (Pol) The test purpose in terms of Characterization, Verification, or Validation	Characterize the impact use of local flexibility on available regulating power from a local district.
System under Test (SuT):	- Floridad
Systems, subsystems, components included in the test case or test setup.	District Supervisory Control Other physical
	Booster Heater Control District- Integrated Booster Heating Network District Heating PCC Building Electric Storage Control Electric Battery Storage Building Electrical Demand Electric Battery Storage Electric Battery Storage Electric Battery Storage Environ- ment Environ- ment

Functions under Test (FuT) Functions relevant to the operation of the system under test, including Ful and relevant interactions btw. Oul and SuT.	 "PCC" denotes the point of common coupling for the district to the external networks. All units connected downstream of the respective PCCs must be considered. electrical and heat exchange (at respective PCC) electrical energy bound violation total district electricity export
	total district thermal energy import
Test criteria (TCR) Formulation of criteria for each Pol based on properties of SuT; encompasses properties of test signals and output measures.	The TCR (test criteria) aim to quantify the resource and service conflicts: 1) the export/import from the electrical distribution network (including the respect for capacity limitations); 2) the service level at the district heating network (energy and service level violations)
Target Metrics (TM) Measures required to quantify each identified test criteria	 electrical energy bound violation in MWh: given a limit P_t^{max} for t ∈ T' ⊆ T, measure the violation via the total electrical energy consumption as E_{bound} = ∑_{t∈T'} f (P_t^{tot} - P_t^{max}), where f is a one-sided error measure, e.g. f(x)=x if x>0, else x=0.
	 electrical and heat exchange (at respective PCC) in MWh
	total district electricity export in MWh
	 total district thermal energy import in MWh
Variability Attributes (VA) controllable or uncontrollable factors and the required variability; ref. to Pol.	Controllable factors:
Quality Attributes (QA) threshold levels for test result quality as well as pass/fail criteria.	N/A

Qualification Strategy

The Pol is addressed first using a simple implementation to verify the test concept and the functional principles, the outcome of TS01 is a preliminary characterisation of the same TCR as TS02. TS02 will then refine and validate the characterisation on a more realistic study case.

Test Specification TC11.TS01


Reference to Test Case	TC11
Title of Test	Local controller responds to service requests from aggregator controller
Test Rationale	This test characterizes district operation of a simple long district heat pipe with heat booster HP and without Booster Heater Controller and Electric Storage Controller active, seeking to demonstrate that the local controllers respond to service requests from the aggregator controller.
Specific Test System (graphical)	The system under test includes an electrical system, a district heating system and a control system. Each is sketched below.
	Thermal system
	The thermal system is a simplified distribution network which includes a booster heat pump. The heat load is aggregated in two locations.
	PCC 2km 1km
	Electrical system Bypass
	The electrical system corresponds to a single feeder.
	10kV —
	₽
	Heat Pump
	Battery
	Control domain coupling


	Heat Network Control Center Distribution Grid Management P_Import_limit[b] P_export_limit[b] P_expor
	under test but are taken as exogenous signals.
Target measures	See Test Design.
Input and output parameters	 P_PCC: Measured apparent electrical import at the district electrical network point of common coupling [kWe] Q_PCC: Measured heat import at the district heating network point of common coupling [kWq] P_booster: Measured electrical active power consumption of district booster heater [kWe]
Test Design	The test comprises 24 hours of district operation. During these 24 hours, the heat pump controller is asked to keep the forward temperature of the connected pipe above 70°C. Further, these services are requested of the Aggregator by the Distribution Grid Management: • for 07:00 to 09:00, keep district electrical consumption below P_import_limit kW • for 11:00 to 14:00, keep district electrical consumption above P_export_limit kW. • for 17:00 to 19:00, keep district electrical consumption below P_import_limit kW where these limits are defined as below. The test consists of several runs: 1) no service signal sent 2) service signals sent (gamma indicates the level of service requested – lower gamma = more service requested) a) gamma = 1.0 b) gamma = 0.95 c) gamma = 0.95 c) gamma = 0.85 e) gamma = 0.80 By comparing these runs, whether the controllers respond to service requests can be established. For run 1, set: • P_import_limit = inf,

	For subsequent runs (given the 99% quantile of district electrical
	import P_i_99 and the 1% quantile of district electrical import,
	P_i_1), the system is asked to restrict its import relative to the un-
	controlled base case:
	P_export_limit= gamma * P_i_1 kWe
	 P_import_limit = gamma* P_i_99 kWe,
Initial system state	each component is initialized to the state given in the as-
	sociated dataset
	 the battery state of charge is set to 50% of nomimal en-
	ergy
	 the district heating system is allowed to relax to a steady
	state with the heat pump turned off
Evolution of system state and	Test signals:
test signals	 P_import_limit: District electrical consumption bound re-
	quested from battery/EV units [kWe]
	 P_export_limit: District electrical export bound requested
	from heating units [kWe]
	 gamma: Scaling factor for district import and export [n.u.]
Other parameters	N/A
Temporal resolution	The test is run at a fixed time step of 10 seconds.
Source of uncertainty	Since the exact electrical demand signal consists of a deterministic
	trend and a randomized factor, each "run" above should be re-
	peated 10 times, with the mean and standard deviation of each tar-
	get metric recorded.
Suspension criteria / Stopping	N/A
criteria	

Test Specification TC11.TS02

Reference to Test Case	TC11
Title of Test	Local controller responds to service requests from aggregator con-
	troller
Test Rationale	This test characterizes district operation with and without Booster Heater Controller and Electric Storage Controller active, seeking to demonstrate that the local controllers respond to service requests from the aggregator controller.
Specific Test System (graphical)	The system under test includes an electrical system, a district heating system and a control system. Each is sketched below. Thermal system
	The block called "Row Houses" consists of multiple small loads which are aggregated into a single, larger load.





	i) gamma 0.00
	j) gamma = 0.80
	By comparing these runs, whether the controllers respond to service requests can be established.
	For run 1, set: • P_import_limit = inf, • P_export_limit = -inf • gamma=1.0.
	For subsequent runs (given the 99% quantile of district electrical import P_i_99 and the 1% quantile of district electrical import, P_i_1), the system is asked to restrict its import relative to the uncontrolled base case:
	P_export_limit= gamma * P_i_1 kWe P_import_limit = gamma * P_i 00 kWe
Initial system state	 P_import_limit = gamma* P_i_99 kWe, each component is initialized to the state given in the as-
initial system state	sociated dataset
	the battery state of charge is set to 50% of nomimal en-
	ergy
	the district heating system is allowed to relax to a steady
	state with the heat pump turned off
Evolution of system state and	Test signals:
test signals	 P_import_limit: District electrical consumption bound requested from battery/EV units [kWe]
	 P_export_limit: District electrical export bound requested from heating units [kWe]
	 gamma: Scaling factor for district import and export [n.u.]
Other parameters	N/A
Temporal resolution	The test is run at a fixed time step of 10 seconds.
Source of uncertainty	Since the exact electrical demand signal consists of a deterministic
	trend and a randomized factor, each "run" above should be re-
	peated 10 times, with the mean and standard deviation of each tar-
Suspension criteria / Stopping	get metric recorded. N/A
criteria	N/A
UITEITA	

Mapping to Research Infrastructure

The test specifications are implemented in several co-simulation setups. The reference implementation for TS01 is a pure Python / Mosaik implementation; the reference implementation for TS02 is a co-simulation using Dymola, PandaPower and Mosaik as orchestrator.

Experiment Specification ##.##.##

Reference to Test Specification	
Title of Experiment	
Research Infrastructure	
Experiment Realisation	
Experiment Setup	
(concrete lab equipment)	
Experimental Design and	
Justification	
Precision of equipment and	
measurement uncertainty	
Storage of experiment data	