Test Case 4

Author G. Coletta (RSE), L. Pellegrino (RES), E. Rikos (CRES), V.S. Rajkumar (TUD), M.Z. Degafa (SINTEF), O. Gehrke (DTU)

Version 0.1

Project ERIGrid 2.0 Date 17.02.2023

Name of the Test Case	Multi-Energy District Flexibility	
Narrative	This test aims to investigate the power-to-heat service provision in a local multi-energy district and its impact on the electric and thermal networks. The flexibility requested by the DSO can be provided by a combination of electric and thermal storage systems as well as flexible controllable loads, such as Heat Pumps, Thermal Loads, Electric Boilers, etc.	
Function(s) under Investigation (Ful) "the referenced specification of a function realized (operationalized) by the object under investigation"	The heating system provides services to the electrical system (a) congestion management - electrical import and export limitation; and (b) regulating power provision.	
Object under Investigation (Oul) "the component(s) (1n) that are to be qualified by the test"	The characterization concerns the Centralized Supervisory Controller (CSC) of a local multi-energy system.	
Domain under Investigation (<i>Dul</i>): "the relevant domains or sub-domains of test parameters and connectivity."	Electrical domain Thermal domain Control and ICT systems	
Purpose of Investigation (Pol) The test purpose in terms of Characterization, Verification, or Validation	Verification of the impact of local flexibility on available regulating power from a local district.	
Systems, subsystems, components included in the test case or test setup.	Booster Heater Control District Integrated Booster Heating Control District Integrated Booster Heating Network District Heating PCC District Heating Heat Demand Demand Demand Environ- ment PCC" denotes the point of common coupling for the district to the external networks. All units connected downstream of the	

	respective PCCs must be considered.
Functions under Test (FuT) Functions relevant to the operation of the system under test, including Ful and relevant interactions btw. Oul and SuT.	 P-f and Q-v control of single devices. Local district CSC Services provision by the CSC
Test criteria: Formulation of criteria for each Pol based on properties of SuT; encompasses properties of test signals and output measures.	The TCR (test criteria) aims to verify the ability of the local district to provide services to the electric network: • Congestion management • Active power control at the electric network PCC • Regulating power provision
target metrics Measures required to quantify each identified test criteria	The measure required: • electrical energy bound violation [MWh]: given a limit P_k^{max} of a system component $k \in K$ (e.g. power line, power transformers, electric bus, etc.) at $t \in T' \subseteq T$, measure the energy violation as: $E_k^{bound} = \sum_{t \in T'} (P_{k,t} - P_k^{max})^+$ • electrical energy balance deviation [MWh]: given a set point P_{PCC}^{set} at the electric network PCC at $t \in T' \subseteq T$, measure the energy violation as: $E_{set} = \sum_{t \in T'} P_{PCC,t} - P_{PCC,t}^{Set} $
variability attributes controllable or uncontrollable factors and the required variability; ref. to Pol.	Controllable factors: • heat pumps set-point • electrical and thermal storage system set-point Uncontrollable factors: • demand (electrical and thermal) • PV generation
quality attributes threshold levels for test result quality as well as pass/fail criteria.	n/a

Qualification Strategy


The Pol is addressed through the implementation of a single Test Specification (TS1), which includes multiple RIs. A first phase (ES1) will verify the ERIGrid 2.0 extended research infrastructure capability and set-up the main experiments:

- ES2: Congestion management
- ES3: Active power control at the electric network PCC
- ES4: Regulating power provision

Test Specification D4.1

Reference to Test Case	TC D4

Title of Test	CSC service provision verification.	
Test Rationale	This test verifies the local district operation seeking to demonstrate that the CSC respond to a service request: Congestion management Active power control at the electric network PCC Regulating power provision	
Specific Test System (graphical)	The system under test includes an electrical system, a district heating system and a control system. Each is sketched below. Thermal system The thermal system is composed by two subsystems, one connected to a District Heating Network (DHN) and interfaced to the electrical system through a Combine Heat and Power (CHP) and another one fed by an Electrical Heat Pump (EHP).	
	Combined Heat and Power (CHP)	
	Const. power source Cosumer 2 Cosumer 1 Const. temp. source	
	CRES Water tank Heat pump Fan Coil Fan Coil	
	Electrical system The electrical system is composed by three main physical feeders and a simulated grid portion. The physical feeders connect a simulated BESS, a CHP and an EHP.	




Other parameters	n/a
Temporal resolution	The test is run at a fixed time step of 15 min.
Source of uncertainty	Since the exact electrical demand signal consists of a deterministic trend and a randomized factor, each "run" above should be repeated 10 times, with the mean and standard deviation of each target metric recorded.
Suspension criteria / Stopping criteria	n/a

Mapping to Research Infrastructure


The test specifications are implemented in several Quasi-Static PHIL (QS-PHIL) experiments in order to exploit them geographically separated over several research facilities.

Experiment Specification ES.D4.1




total for two lines w/ forward and return circuit each)

- The load in the middle of the line is the controllable heating system (water-to-air heat exchangers) of a laboratory hall.
- The load at the end of the line is a controllable heat dumpload.
- Measurements at each bay: Tforward, Treturn flow, differential pressure
- Distributed temperature measurements (forward+return) along each line, every 100 m.



Energy Storage Systems (ESS) (SINTEF)

- Converter with a nominal capacity of 50KVA
- Power amplifier (200 KVA) with 700 V DC and 400 V AC ports
- · BESS emulator
- Measurement points: the state of charge (SoC), instantaneous power from the battery.




CHP (RSE):

• CHP plant with a NG Internal combustion engine (50kWe,

81 kWth);


- 1 Bidirectional DC/AC Front-end-converter (30 kVA)
- 1 Bidirectional B2B converter (30 kVA)
- Three-phase LV grid



Experimental Design and Justification

This test case aims to validate the capability of the extended research infrastructure for real-world multi-energy system experiments. The use of the extended research infrastructure increases the reality of the experiment by including real components and real-world user behavior.

Precision of equipment and measurement uncertainty



- M1: Active power and voltage magnitude at the SINTEF facility;
- M2: Active power and voltage magnitude at the RSE facility;

Quantity	% Full Scale		
	0-5 %	5-20 %	20-100 %
Voltage		0.20%	
Current	3.03%	1.55 %	1.08 %
Active Power	3.06%	1.62 %	1.17 %
Reactive Power	3.19 %	1.86 %	1.48 %
Apparent Power	3.06%	1.62 %	1.17 %
Frequency		\pm 0.10 ml	Hz

	 M3: CHP active power (RSE); Same (M2) M4: EHP active power (CRES); Precision=0.01kW M5-M7: Temperature and mass flow (DTU); M6: CHP Temperature and mass flow (RSE); Mass flow Accuracy: _ 0.5 kg/s Temperature Accuracy: _ 0.2 K M8-M9: Temperature and mass flow (CRES); Temperature precision = 0.1 °C
Storage of experiment data	Data of each facility will be stored in a separate database at the experiment temporal resolution with a common temporal reference.

Experiment Specification ES.D4.2

Reference to Test Specification	TS D4.1
Title of Experiment	Congestion management
Research Infrastructure	RSE, CRES, DTU, TUD, SINTEF
Experiment Realisation	Initlal conditions definition
	Control system implementation
	Experiment execution
Experiment Setup	See ES D4.1
(concrete lab equipment)	
Experimental Design and	This test case aims to demonstrate the ability of a multi-
Justification	energy district to solve or mitigate congestion on the electric
	power distribution network.
Precision of equipment and	See ES D4.1
measurement uncertainty	
Storage of experiment data	See ES D4.1

Experiment Specification ES.D4.3

Reference to Test Specification	TS D4.1
Title of Experiment	Active power control at the electric network PCC.
Research Infrastructure	RSE, CRES, DTU, TUD, SINTEF
Experiment Realisation	Initlal conditions definition
	Control system implementation
	Experiment execution
Experiment Setup	See ES D4.1
(concrete lab equipment)	
Experimental Design and Justification	This test case aims to demonstrate the ability of a multi- energy district to limit power absorption at the electric net- work PCC.
Precision of equipment and measurement uncertainty	See ES D4.1
Storage of experiment data	See ES D4.1

Experiment Specification ES.D4.4

Reference to Test Specification	TS D4.1
Title of Experiment	Balancing power provision.
Research Infrastructure	RSE, CRES, DTU, TUD, SINTEF
Experiment Realisation	Initlal conditions definition
	Control system implementation
	Experiment execution
Experiment Setup	See ES D4.1
(concrete lab equipment)	
Experimental Design and	This test case aims to demonstrate the ability of a multi-
Justification	energy district to limit power absorption at the electric net-
	work PCC.
Precision of equipment and	See ES D4.1
measurement uncertainty	
Storage of experiment data	See ES D4.1